
```
## Registered S3 method overwritten by 'xts':
## method from
## as.zoo.xts zoo

## Registered S3 method overwritten by 'quantmod':
## method from
## as.zoo.data.frame zoo
```



```
--- Base Sewer Flow (kGPD) -----
##
##
   Weekday: 551.9
##
   Weekend: 576.3
##
##
   --- Peaking Factor ------
               90%
                       95%
                              99%
##
##
   Weekday:
              2.1
                     2.16
                            2.46
##
   Weekend:
              1.98
                      2.08
                             2.21
##
   --- Ground Water Infiltration (kGPD) -----
##
    5%: 322.8 ( 224.2 gpm )
##
##
   95%: 730 (506.9 gpm)
##
   99%: 856.4 (594.8 gpm)
##
   --- Rainfall Derived Inflow (GPM) -----
##
##
         6-hour SCS Type-II Storm
           100
##
   MA:
```

```
## 5-YR: 122.7
## 25-YR: 189.4
## 100-YR: 265.5
##

Total Volume: 9.09 kGal/inch ( 18.73 acre )
##

## --- Peak Hourly Flow (GPM) -----
## DWF (95%): 1340.5
## WWF (99%): 1727.2 (25-YR 6-HR)
```